No.	Items of work	Unit	Rate	Quantity	Cost
			Rs. a. p.		
9	Lime mortar plastering 2 coats over brick work	Sqr.	3 8 0	93·06	326
10	White washing 2 coats inside and colour washing 2 coats outside	,,	0 5 0	93·06	29
11	Burnt brick in lime mortar cornice 12″ deep (modern design) as per drawing including smooth lime mortar plastering and colour washing, etc., complete	R.ft.	0 10 0	376	285
12	Burnt brick in lime mortar parapet wall 2½′ high and 9″ thick with R.C.C. panels in alternate bays as per drawing including plastering with lime mortar and colour washing	R.ft.	1 8 0	403	605
13	W. I. railing as per design including teakwood polished hand rail (3″×4″) 2¾′ high with 2 coats of approved paint	,,	2 8 0	113	283

N. KRISHNEINGAR,
Executive Engineer.

TUMKUR DIVISION.

Notification dated 17th November 1936.

1. Sealed tenders will be received at the office of the Executive Engineer, Tumkur Division, up to 2 P.M. on 14th December 1936.

2. Tenders in the prescribed form obtainable from the office of the Executive Engineer, Tumkur Division, on payment of Rs.....Each form should be addresssed to the Executive Engineer, Tumkur Division and should be superscribed as "tender for restoring Kanakuppe Tank". The name of the tenderer should also be superscribed on the sealed cover.

3. Each tender must be accompanied by a deposit of Rs. 800 in words (Rupees eight hundred only) in cash or Government Promissory Notes of Mysore Government Bonds at face value or market value whichever is less as earnest money. The earnest money of the successful tenderer will be retained as security deposit for due fulfilment of the contract (cash amount will not carry any interest.)

4. The tenders will be opened in the presence of such contractors who wish to be present on ..... The final acceptance of the tender will rest with the Superintending Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any.

5. The names of the successful tenderer will be posted on the Notice Board in the Executive Engineer's Office in due course. Within 8 days of the acceptance of the tender, the successful tenderer will be required to execute an agreement in the Departmental Schedule contract form for the due fulfilment of the contract.

6. Failure to comply with the condition 5 above or to agree to carry out the work in accordance with the specifications and agreements in force will entail forfeiture of the earnest money.

7. Copies of contract documents, estimates and drawings may be seen at any time at the Executive Engineer's Office, Tumkur Division, on all working days between 11 A.M. to 5 P.M.

8. Specific rates should be given for each item in the Schedule and the rates should be in rupees, annas and in multiple of three pies and expressed in words and figures. Tenderers offering a percentage reduction on the estimate amount will be rejected.

9. Any rates or lumpsum amounts for the items not called for, if tendered by the tenderer, will not be taken notice of. The rates tendered should include all such lumpsum items.

10. No alterations which are made by the tenderers in the contract documents in the nomenclature of the sanctioned sub-heads will be recognised and if corrections are made the tenders will be liable to rejection.

11. There should be no corrections or erasures in the tenders in the rates of items and any corrections made in the rates should be attested to and the number of corrections, if any, in each page noted at the foot of the same by the tenderer.

12. No reference should be made to the Public Works Department for current schedule of rates.

13. On the event of the tender being submitted by a firm, it must be signed separately and severally by each number thereof or in the event of absence of any partner, it must be signed on his behalf by a person holding power of attorney authorising him to do so.

14. When once the rates tendered have been accepted they will not be revised under any circumstances. In regard to items of work not tendered, the rates to be proposed by the Executive Engineer and approved by the Superintending Engineer shall be final and legally binding on the tenderer.

15. The quantities given in the schedule are only approximate and are liable to alterations, omissions, deductions, or additions at the discretion of the Executive Engineer or his representative. The tendered rates will hold good for any quantity whether higher or lower than those given in the enclosed schedule.

16. The works should be completed and handed over to the Public Works Department by the end of month, to be fixed by the Executive Engineer, failing which the Executive Engineer may at his discretion levy a penalty of Rs.....per day which will be recovered from the contractor's out-standings for the period exceeded by him till the work is completed and handed over.

17. In all matters of disputes of any kind not specially provided for in the agreement or of rates, penalties, measurements, quantity of work, etc., the decision of the Chief or the Superintending Engineer shall be final and legally binding.

18. The earnest money of rejected tenders will be returned on submission of the receipt originally granted, along with the application, to the Executive Engineer.

19. No claim for damages for delays caused by officers of the Department in the execution of the work will be considered, whatever may be the reasons for such delays. Contractors should bear this in mind when tendering for the work. Extension of time due to delays caused by the Departmental officers will however be considered on the merits of each case.

20. The contract should not be sub-let.

Abstract estimate for restoring Kanakuppe Tank, Registered No. 267, Tumkur Taluk.

No.	Items of work	Per	Rate	Quantity
	Bund.		Rs. a. p.	
1	Earthwork cutting grips	C.yd.	0 3 6	660
2	Earthwork to bund with watering and tamping ..	,,	0 4 0	12,507
3	Turfing	S.yd.	0 1 0	21,173
4	Supplying and fixing grade stones	Each	2 8 0	41
5	Do Index stones	,,	0 8 0	41
6	Do Register No. stone	,,	5 0 0	1
7	Do B. M. stones	,,	3 0 0	2
8	Do Gauge stone	,,	15 0 0	1
	Sluices No. 1 and 2.			
1	Constructing sluice with Bhadravati C. I. pipe 12″ dia. including rendering joints water tight with red lead hemp and lead wool including masonry collars over concrete bed			
	No. 1 sluice at R. L. 43.00 in C.S. 8	R.ft.	10 0 0	60
	No. 2 sluice at R. L. 43.00 in C.S. 37	R.ft.	10 0 0	62
	Breach filling in C.S. 6 and 7.			
1	Clearing silt and sand	C.yd.	0 2 6	1,067
2	Earthwork cutting steps and grips	..	0 3 6	612
3	Burnt brick in surki mortar	C.ft.	0 4 0	1,344
4	Earthwork to breach with mixture earth	C.yd.	0 4 0	6,952
5	Rough stone revetment (new)	,,	1 12 0	601
6	Gravel backing behind revetment	..	0 6 0	200
7	Turfing	S.yd.	0 1 0	496
8	Baling water in foundation	L.S.	..	..
	Constructing left Waste Weir 200 feet long at R.L. 48.50.			
1	Earthwork excavation foundation and draft clearing ..	C.yd.	0 3 6	898
2	Stone jelly concrete in surki mortar	C.ft.	0 4 0	1,032
3	Burnt brick in surki mortar	,,	0 4 0	4,556
4	Providing and fixing burnt stone slabs 6″ thick with joggle joints and dressing faces, etc., complete	S.ft.	0 10 0	658

No.	Items of work	Per	Rate	Quantity
			Rs. a. p.	
5	Plastering with surki mortar	Sqr.	3 12 0	37.48
6	Rough stone apron	C.yd.	1 12 0	653
7	Rough stone wings	..	1 12 0	39
8	Jelly filling below apron	..	0 8 0	306
9	Old stone work for four binding walls	..	1 0 0	214
	Constructing Waste Weir at right end 160 feet long at R. L. 48.50.			
1	Earthwork excavation for foundation	C.yd.	0 3 6	198
2	Stone jelly concrete in surki mortar	C.ft.	0 4 0	943
3	Burnt brick in surki mortar	,,	0 4 0	4,467
4	Providing and fixing burnt stone slabs 6" thick with joggle joints and dressing faces, etc., complete ..	S.ft.	0 10 0	500
5	Plastering with surki mortar	Sqr.	3 12 0	38.16
6	Rough stone apron	C.yd.	1 12 0	284
7	Rough stone wings	..	1 12 0	39
8	Jelly filling below apron	..	0 8 0	124

N. G. KRISHNAIENGAR,
Executive Engineer.

MEDICAL DEPARTMENT

PRINCESS KRISHNAJAMMANNI TUBERCULOSIS SANATORIUM, MYSORE.

ABSTRACT OF THE TENDER NOTIFICATION OF DIETING ARTICLES OF P. K. T. SANATORIUM, MYSORE, FOR THE YEAR 1936.

Tender Notice, dated 24th October 1936.

Notice is hereby given that sealed tenders, in triplicate, on half-sheet foolscap-sized paper will be received at the Office of the Medical Officer, Princess Krishnajammanni Tuberculosis Sanatorium, Mysore, at 4 P.M., on the 9th December 1936, for the supply of articles of diet, etc., (as per list annexed), required for the use of the Princess Krishnajammanni Tuberculosis Sanatorium, Mysore, from 1st January to 31st December 1937 (both days inclusive).

2. No tender will be received after the date and hour abovementioned.

3. Tenders should be superscribed " Tender for the supply of provisions to the Princess Krishnajammanni Tuberculosis Sanatorium, Mysore, for the year 1937."

4. No tender will be received unless accompanied by a receipt for Rs. 200 deposited in any of the Government Treasuries in the State as earnest money for tender to the credit of the Medical Officer, Princess Krishnajammanni Tuberculosis Sanatorium, Mysore. No cash payment will be accepted.

5. Tenders will be opened by the Medical Officer in charge at his office on the date and at the hour abovementioned in the presence of such tenderers as may choose to attend.